

ARR0001550

MURRAWOMBIE COPPER MINE ANNUAL REHABILITATION REPORT

Monday 1 July 2024 to Monday 30 June 2025





Summary table

DETAIL	
Mine	Murrawombie Copper Mine
Reference	ARR0001550
Annual report period commencement date	Monday 1 July 2024
Annual report period end date	Monday 30 June 2025
Forward program	FWP0001463
Mining leases	MPL 294 (1973), MPL 295 (1973), ML 1280 (1973)
Lease holder(s)	Tritton Resources Pty Ltd
Contact	Mike Fake

Date of submission Friday 5 September 2025

Important

The department may make the information in your report and any supporting information available for inspection by members of the public, including by publication on its website or by displaying the information at any of its offices. If you consider any part of your report to be confidential, please communicate this to the department via the message function on this submission within the NSW Resources Regulator Portal.

Mine details

Project description

The Mine is located approximately 3.5km west of the village of Girilambone within the Bogan Local Government Area (LGA) in central west NSW. The Mine is owned and operated by Tritton Resources Pty Ltd (the "Company"), a wholly owned subsidiary of Aeris Resources Limited. Operations at the Mine commenced under Development Application (DA) 1/91 and Mining Lease (ML) 1280 in 1992. DA 1/91 was issued by Bogan Shire Council and does not contain an expiry date. The Mine operation comprises of an open cut pit, a box cut decline portal to the Murrawombie underground mine, a heap leach copper extraction circuit and maintenance and administrative activities. The ore extracted from the underground operation is transported to the run of mine (ROM) pad at the surface where it is stored prior to being hauled to the Tritton Mine for processing via Yarrandale Road. Open cut operations have resumed with the cutback of the pit. Waste rock from the cutback is being used to close the heap leach pads.

Life of mine

30 years

Current development consents, leases and licences

Development consents granted under the Environmental Planning and Assessment Act 1979

10/2028/027/001 2010/022 5/95 1/91 2010/029

Authorisations covering the mining area granted under the Mining Act 1992

```
MPL 294 (1973), MPL 295 (1973), ML 1280 (1973)
```

Any other approvals, licences, or authorities issued by government agencies that are relevant to the progress of mining operation and rehabilitation activities

EPL4501			

ARR0001550 | Monday 1 July 2024 to Monday 30 June 2025



Summary of the scope and/or purpose of the new applications or modifications to existing approvals (if applicable)

Modification 5 to DA1/91 was granted 4 July 2024. Modification 5, like the previous modification, seeks to facilitate the cutback of the open cut pit through relocation of ancillary mining infrastructure. Other changes to surface infrastructure were made to facilitate closure of the Heap Leach Pad facility through construction of the Rock Storage Facility which encapsulates the HLP.

Changes to land ownership and land use

N/A

Surface disturbance and rehabilitation activities during the reporting period

Surface disturbance and rehabilitation activities that were conducted and an analysis of the progress against the rehabilitation schedule

Areas that were disturbed for the historical surface mining operations and subsequently stabilised with vegetation were reactivated to support safe recommencement of open cut mining. Undisturbed areas within the approved footprint of the Southern WRE were disturbed for the construction of the approved ROM Pad and stockpiling areas. All disturbance was in accordance with DA1/91. The reactivation of historic mining areas was not identified in the previous FWP as need to relocate certain infrastructure

Rehabilitation planning activities that were conducted, including any specialist studies

- The design of the RSF was finalised. Key objectives of the RSF design are to encapsulate the buried spent leach material as well as all PAF material mined during the cutback. The key function of the RSF is to minimise net percolation and potential for leaching as far as reasonably practicable. - The design of the capping layer for the HLP was finalised. The design uses a typical "store and release" cover system that together with the RSF further reduces risk of net percolation and leaching from the facility. The cap utilises the existing water management infrastructure of the facility as water retention and evaporation basins. - geotechnical assessments of the RSF and pit/RSF interactions were undertaken to confirm the suitability of the design and inform long-term stability / closure planning.

Overview	of cubcidonce	ropair and	or romodiation	works undertaken
Overview (oi subsidence	: revair anu/	or remediation	works undertaken

Nil

Overview of rehabilitation management and maintenance activities

General site maintenance and monitoring activities. No targeted works undertaken

Details of any rehabilitation actions taken as required by any letters, notices or directions issued by government agencies, including the NSW Resources Regulator

Nil

ARR0001550 | Monday 1 July 2024 to Monday 30 June 2025



Details of any rehabilitation areas that have achieved the final land use

Nil

Key production milestones

MATERIAL	UNIT	FWP0001463 YEAR 1	THIS REPORT
Stripped topsoil (if applicable)	(m³)	0	30,048
Rock/overburden	(m³)	2,261,597	1,011,240
Ore	(Mt)	0.29	3,193
Reject material ¹	(Mt)	0.27	0.15
Product	(Mt)	0.01	0.04

 $^{^{\}mathrm{1}}$ This includes coarse rejects, tailings and any other wastes resulting from beneficiation.



Disturbance and rehabilitation statistics

Current disturbance and rehabilitation progression

	ELEMENT	UNIT	THIS REPORT
A1	Total disturbance footprint – surface disturbance	(ha)	230.34
В	Total active disturbance	(ha)	130.2
С	Rehabilitation – land preparation	(ha)	57.03
D	Ecosystem and land use establishment	(ha)	0
E	Ecosystem and land use development	(ha)	43.12
F	Rehabilitation completion	(ha)	0

Rehabilitation key performance indicators (KPIs)

ELEMENT	UNIT	THIS REPORT
G New disturbance area	(ha)	4.26
H New rehabilitation commenced during annual reporting period	(ha)	56.92
I Established rehabilitation	(ha)	43.12
J Annual rehabilitation to disturbance ratio	%	13.36
K Rehabilitated land to total mine footprint	%	18.72

Progressive achievement of established rehabilitation

	ELEMENT	UNIT	THIS REPORT
L	Established rehabilitation for agricultural final land uses	%	0
M	Established rehabilitation for native ecosystem final land uses	%	100
N	Established rehabilitation for other/non-vegetated final land uses	%	0

Variation to the rehabilitation schedule

Identify the components of the most recent forward program that were not achieved

Nil

Key factors that delayed progressive rehabilitation

Nil

Outline actions that will be included in the forward program and carried out to minimise disturbance and undertake progressive rehabilitation as far as reasonably practical

Nil

Rehabilitation monitoring and research findings

Rehabilitation monitoring

The rehabilitation monitoring carried out in the annual reporting period

No monitoring or reporting was undertaken during the reporting period.

Status of performance against rehabilitation objectives and rehabilitation completion criteria

The monitoring program that has been implemented

Analogue monitoring sites have been established at the North East Copper Mine to derive reference values for Woodland and Grassland systems. Woodlands and grasslands rehabilitation monitoring sites have been established on the WREs at MCM. Monitoring occurs on a triennial basis. TCM and NECM have similar monitoring sites but are reported separately.

Are all rehabilitation areas in Landform Establishment phase or higher represented in the monitoring program to assess performance against the rehabilitation objectives and approved or, if not yet approved rehabilitation completion criteria and final landform and rehabilitation plan?

Yes

Year rehabilitation areas will be included as part of the monitoring program

An appraisal of whether rehabilitation is moving towards achieving the proposed rehabilitation objectives, approved or, if not yet approved, rehabilitation completion criteria and final landform and rehabilitation plan as soon as reasonably practicable.

Rehabilitation performance across all monitoring sites varied based on age, construction and substrates, which significantly influences the ability of vegetation to become established. Unstable and/or undesirable spoil characteristics have also impacted performance of certain sites. Rehab sites generally are responding to local and regional climatic influences similar to reference sites. Intra-site composition varied however composition was generally consistent across all sites.

Appraisal description

There are performance issues preventing rehabilitation moving towards achieving the final land use as soon as reasonably practicable.

ARR0001550 | Monday 1 July 2024 to Monday 30 June 2025



Rehabilitation monitoring program findings

No formal monitoring undertaken. The next round of monitoring will be undertaken in the next reporting period.

Performance issues and their causes including identification of any knowledge gaps that must be addressed

Rehabilitation has had mixed results. Rehabilitation of surface disturbance from open cut mining has generally progressed well. However rehabilitation of the WREs has been impacted by several factors which are preventing successful rehabilitation across the landforms.



Outcomes of rehabilitation research and trials

RRT NUMBER	PROJECT/TRIAL NAME	OBJECTIVE OF TRIAL/PROJECT	METHODOLOGY	EXPECTED DATE OF COMPLETION	STATUS	ON TRACK?

A RR0001550

ARR0001550 | Monday 1 July 2024 to Monday 30 June 2025

NSW Resources Regulator

Outcomes of completed trials and research	Outcomes	of cor	mpleted	trials	and	research
---	----------	--------	---------	--------	-----	----------

N/A

Attachment 1 – Reporting Definitions

REP	ORTING CATEGORY	DEFINITION
A1	Total disturbance footprint – surface disturbance	All areas within a mining lease that either have at some point in time or continue to pose a rehabilitation liability due to surface disturbance activities.
		The total disturbance footprint is the sum of the total active disturbance, decommissioning, landform establishment, growth medium development, ecosystem and land use establishment, ecosystem and land use development and rehabilitation completion (see definitions below).
		Underground mining operations should not include the footprint of underground mining areas/subsidence management areas in the total disturbance footprint.
A2	Underground Mining Area	Underground mining operations areas/subsidence management areas.
В	Total active disturbance	Includes on-lease exploration areas, stripped areas ahead of mining, infrastructure areas, water management infrastructure, sewage treatment facilities, topsoil stockpile areas, access tracks and haul roads, active mining areas, waste rock emplacements (active/unshaped/in or out-of-pit), tailings dams (active/unshaped/uncapped) and temporary stabilised areas (e.g. areas sown with temporary cover crops for dust mitigation and temporary rehabilitation).
C	Rehabilitation – land preparation	Includes the sum of all disturbed land within a mining lease that have commenced any, or all, of the following phases of rehabilitation – decommissioning, landform establishment and growth medium development. Refer to the glossary of terms in this document for the definition of these phases of rehabilitation.

REP	ORTING CATEGORY	DEFINITION
D	Ecosystem and land use establishment	Includes the area which has been seeded/planted with the target vegetation species for the intended final land use. However, vegetation has not matured to a stage where it can be demonstrated that it will be sustainable for the long term and or require only a maintenance regime consistent with target reference/analogue sites.
		Typically, rehabilitation areas would be in this phase for at least two years (and usually more) before rehabilitation can be classified as being in the ecosystem and land use development phase. This phase does not apply to infrastructure areas that are being retained as part of final land use for the site.
E	Ecosystem and Land Use Development	Rehabilitation has matured to a level where target revegetation outcomes are on a trajectory towards meeting the final rehabilitation objectives and rehabilitation completion criteria (as verified by monitoring).
		This phase includes infrastructure areas that are to be retained for an approved post mining land use, following completion of all necessary measures to render the infrastructure fit for this purpose (for example structural integrity).
F	Rehabilitation Completion	The NSW Resources Regulator has determined in writing that the mining area has achieved the approved rehabilitation objectives and approved rehabilitation completion criteria and final landform and rehabilitation plan following the submission of Form: ESF2 Rehabilitation completion and/or review of rehabilitation cost estimate and/or notification of mine or petroleum site closure.
G	New active disturbance area	The area of any new active disturbance that has been created during the annual reporting period (definition A1 in Table 5).
Н	New rehabilitation commenced during annual reporting period	The sum of any new rehabilitation commenced in the annual reporting period. These areas may be in the rehabilitation land preparation phase or the ecosystem & land use establishment phase (definitions C and D in Table 5).
1	Established rehabilitation (hectares)	The total area of land that is verified to be within either the ecosystem and land use development phase or the rehabilitation completion phase (definitions E & F in Table 5).



REP	ORTING CATEGORY	DEFINITION
J	Annual rehabilitation to disturbance ratio	The rehabilitation to disturbance ratio (H/G) indicates how many hectares of new rehabilitation are undertaken for each hectare of land disturbed during the year. A ratio of 1/1 indicates that the area of new rehabilitation and disturbance in that year are the same.
К	% Rehabilitated land to total mine footprint	The proportion of the total mine footprint (area of land that has been disturbed by past or present surface disturbance activities) that has established rehabilitation (I/A1 x 100). For open cut mining, the proportion of the total mine footprint verified to be "established rehabilitation" should substantially increase as an operation progresses towards mine closure.
L	Established rehabilitation for agricultural final land uses (hectares)	The percentage of total area of land that is verified to be within either the ecosystem and land use development phase or the rehabilitation completion phase (definitions E & F in Table 5) that have been returned to an agricultural final land use.
M	Established rehabilitation for native ecosystem final land uses (hectares)	The percentage of total area of land that is verified to be within either the ecosystem and land use development phase or rehabilitation completion phase (definitions E & F in Table 5) that have been returned to native ecosystem final land use.
N	Established rehabilitation for other/non-vegetated final land uses (hectares)	The percentage of total area of land that is verified to be within either the ecosystem and land use development phase or the rehabilitation completion phase (definitions E & F in Table 5) that have been returned to other/non-vegetated final land use.



Attachment 2 – Definitions

WORD	DEFINITION			
Active	In the context of rehabilitation, land associated with mining domains is considered 'active' for the period following disturbance until the commencement of rehabilitation.			
Active mining phase of rehabilitation, the active mining phase of rehabilitation content of rehabilitation activities undertaken during mining operations such as salvand managing soil resources, salvaging habitat resources, and native seed content phase also includes management actions taken during operations to management action outcomes such as selective hand waste rock and management of tailings emplacements.				
Analogue site	In the context of rehabilitation, an analogue site is a 'reference site' that represents an example of the defining characteristics (such as vegetation composition and structure or agricultural productivity) of the final land use. Characteristics of analogue sites can be assessed to develop the rehabilitation objectives and completion criteria for final land use domains.			
Annual rehabilitation report and forward program	As described in the Mining Regulation 2016.			
Annual reporting period	As defined in the Mining Regulation 2016.			
Closure	A whole-of-mine-life process, which typically culminates in the relinquishment of the mining lease. It includes decommissioning and rehabilitation to achieve the approved final land use(s).			
Decommissioning	The process of removing mining infrastructure and removing contaminants and hazardous materials.			
Decommissioning Phase of Rehabilitation	Activities associated with the removal of mining infrastructure and removal and/or remediation of contaminants and hazardous materials. In the context of the rehabilitation management plan this phase of rehabilitation may also include studies and assessments associated with decommissioning and demolition of infrastructure or works carried out to make safe or 'fit for purpose' built infrastructure to be retained for future use(s) following lease relinquishment.			

WORD	DEFINITION			
Department	The Department of Regional NSW.			
Disturbance	See Surface Disturbance.			
Disturbance area	An area that has been disturbed and that requires rehabilitation. This may include areas such as on-licence exploration areas, stripped areas ahead of mining, infrastructure areas, water management infrastructure, sewage treatment facilities, topsoil stockpile areas, access tracks and haul roads, active mining areas, waste emplacements (active/unshaped/in or out-of-pit), tailings dams (active/unshaped/uncapped), and areas requiring rehabilitation that are temporarily stabilised (i.e. managed to minimise dust generation and/or erosion).			
Domain	An area (or areas) of the land that has been disturbed by mining and has a specific operational use (mining domain) or specific final land use (final land use domain). Land within a domain typically has similar geochemical and/or geophysical characteristics and therefore requires specific rehabilitation activities to achieve the associated final land use.			
Ecosystem and Land Use Development	This phase of rehabilitation consists of the activities to manage maturing rehabilitation areas on a trajectory to achieving the approved rehabilitation objectives and completion criteria. For vegetated land uses this phase may include processes to develop characteristics of functional self-sustaining ecosystems, such as nutrient recycling, vegetation flowering and reproduction, and increasing habitat complexity, and development of a productive, self-sustaining soil profile. This phase of rehabilitation may include specific vegetation management strategies and maintenance such as tree thinning, supplementary plantings and weed management.			
Ecosystem and Land Use Establishment	This phase of rehabilitation consists of the processes to establish the approved final land use following construction of the final landform. For vegetated land uses this rehabilitation phase includes establishing the desired vegetation community and implementing land management activities such as weed control. This phase of rehabilitation may also include habitat augmentation such as installation of nest boxes.			
Exploration	Has the same meaning as that term under the State Environmental Planning Policy (Mining, Petroleum Production and Extractive Industries) 2007.			



WORD	DEFINITION			
Final landform and rehabilitation plan	5 5			
Final land use	As defined in the Mining Regulation 2016.			
Form and way	Means the form and way approved by the Secretary. Approved form and way documents are available on the Department's website.			
Growth Medium Development	This phase of rehabilitation consists of activities required to establish the physical, chemical and biological components of the substrate required to establish the desired vegetation community (including short lived pioneer species.			
	This phase may include spreading the prepared landform with topsoil and/or subsoil and/or soil substitutes, applying soil ameliorants to enhance the physical, chemical and biological characteristics of the growth media, and actions to minimise loss of growth media due to erosion.			
Habitat	Has the same meaning as that term under the <i>Biodiversity Conservation Act 2016</i> and the <i>Fisheries Management Act 1994</i> (as relevant).			
Indicator	An attribute of the biophysical environment (e.g. pH, topsoil depth, biomass) that can be used to approximate the progression of a biophysical process. It can be measured and audited to demonstrate (and track) the progress of an aspect of rehabilitation towards a desired completion criterion (i.e. defined end point). It may be aligned to an established protocol and used to evaluate changes in a system.			
Land	As defined in the <i>Mining Act 1992</i> .			
Landform Establishment	This phase of rehabilitation consists of the processes and activities required to construct the final landform. In addition to profiling the surface of rehabilitation areas to the approved final landform profile this phase may include works to construct surface water drainage features, encapsulate problematic materials such as tailings, and prepare a substrate with the desired physical and chemical characteristics (e.g. rock raking or ameliorating sodic materials).			
Large mine	As defined in the Mining Regulation 2016.			
Lease holder The holder of a mining lease.				



WORD	DEFINITION			
Life of mine	The timeframe of how long a mine is approved to mine, from commencement to closure.			
Mine rehabilitation portal	Means the NSW Resources Regulator's online portal that lease holders must use (via a registered account) to: upload rehabilitation geographical information system (GIS) spatial data develop rehabilitation GIS spatial data (using online tracing functions) generate rehabilitation plans and rehabilitation statistics using the map viewer and Rehabilitation Key Performance Indicator functionalities. Data submitted to the mine rehabilitation portal is collated in a centralised geodatabase for use by the NSW Resources Regulator to regulate rehabilitation performance of lease holders.			
Mining area	As defined in the <i>Mining Act 1992</i> .			
Mining domain	A land management unit with a discrete operational function (e.g. overburden emplacement), and therefore similar geophysical characteristics, that will require specific rehabilitation treatments to achieve the final land use(s).			
Mining land	As defined in the <i>Mining Act 1992</i> .			
Native vegetation	Has the same meaning as that term under section 60B of the <i>Local Land Services Act</i> 2013.			
Overburden	Material overlying coal or a mineral deposit.			
Performance indicator	An attribute of the biophysical environment (for example pH, slope, topsoil depth, biomass) that can be used to demonstrate achievement of a rehabilitation objective. It can be measured and audited to demonstrate (and track) the progress of an aspect of rehabilitation towards a desired completion criterion, that is, a defined end point. It may be aligned to an established protocol and used to evaluate changes in a system.			



WORD	DEFINITION			
Phases of rehabilitation	The stages and sequences of actions required to rehabilitate disturbed land to achieve the final land use. The phases of rehabilitation are: active mining decommissioning landform Establishment growth medium development ecosystem and land use establishment ecosystem and land use development.			
Progressive rehabilitation	The progress of rehabilitation towards achieving the approved rehabilitation completion criteria. This may be described in terms of domains, phases, performance indicators and rehabilitation completion criteria.			
Rehabilitation Completion	The final phase of rehabilitation when a rehabilitation area has achieved the approved rehabilitation objectives and rehabilitation completion criteria for the final land use. Rehabilitation areas may be classified as complete when the NSW Resources Regulator has determined in writing that the relevant rehabilitation obligations have been fulfilled following submission of Form ESF2 Rehabilitation completion and/or review of rehabilitation cost estimate application by the lease holder.			
Rehabilitation Completion criteria	As defined in the Mining Regulation 2016.			
Rehabilitation cost estimate	As defined in the Mining Regulation 2016.			
Rehabilitation management plan	As defined in the Mining Regulation 2016.			
Rehabilitation objectives	As defined in the Mining Regulation 2016.			
Rehabilitation risk assessment	As defined in the Mining Regulation 2016.			
Rehabilitation schedule	The defined timeframes for progressive rehabilitation set out in the forward program.			



WORD	DEFINITION			
Relevant stakeholders				
Risk	The effect of uncertainty on objectives. It is measured in terms of consequences and likelihood (AS/NZS ISO 31000:2009).			
Secretary	The Secretary of the Department.			
Security deposit	An amount that a mining lease holder is required to provide and maintain under a mining lease condition, to secure funding for the fulfilment of obligations under the lease (including obligations that may arise in the future).			
Surface disturbance	Includes activities that disturb the surface of the mining area, including mining operations, ancillary mining activities and exploration.			
Tailings	A combination of the fine-grained solid material remaining after the recoverable metals and minerals have been extracted from the mined ore, and any process water ² .			
Waste	Has the same meaning as that term under the <i>Protection of the Environment Operations Act 1997</i> .			

² Commonwealth of Australia (DITR), 2007. *Tailings Management*.



Attachment 3 – Rehabilitation Complaints

DATE	COMPLAINANT	COMPLAINT DETAILS	RESPONSE DETAILS	STATUS OF RESPONSE	DATE RESPONSE COMPLETED (IF APPLICABLE)
------	-------------	-------------------	------------------	-----------------------	---



Attachment 4 – Stakeholder consultation

DATE	STAKEHOLDER	CONSULTATION ACTIVITIES AND FORMS	MATTERS SUBJECT TO CONSULTATION	ACTIONS TAKEN
19 Mar 202 5	ссс	CCC Meeting	General consultation including rehabilitation	Nil
11 Sep 2024	CCC	CCC Meeting	General operations, including rehabilitation.	Nil.
11 Dec 2024	CCC	CCC Meeting	General operations, including rehabilitation.	Nil.
4 Jun 2025	CCC	CCC Meeting	General consultation including rehabilitation	Nil

ARR0001550 | Monday 1 July 2024 to Monday 30 June 2025



Attachment 5 – Plans

Plan 1a.pdf

Plan 1b.pdf

Annual Report (LARGE MINE) v1.11

Plan 1A: Current Status of Mining and Rehabilitation



current, or otherwise reliable.

THIS MAP IS NOT TO BE USED FOR NAVIGATION

WGS_1984_Web_Mercator_Auxiliary_Sphere

© DRE

Plan 1B: Current Landform Contours



917.2

WGS_1984_Web_Mercator_Auxiliary_Sphere
© DRE

458.62

917.2 Meters

Sydney

Melbourne

Legend

Current Landform Contours

Project Approval Boundary

Mine Operations Area
World Imagery

Low Resolution 15m Imagery High Resolution 60cm Imagery High Resolution 30cm Imagery Citations

Notes

Sub ID:10698

This map is a user generated static output from an Internet mapping site and is for reference only. Data layers that appear on this map may or may not be accurate, current, or otherwise reliable.

THIS MAP IS NOT TO BE USED FOR NAVIGATION